

BUSINESS	
A	215 SF
A/O	150 G
OCC	2

**EXISTING PARKING LOT**

EXISTING N.N.W.

ASSEMBLY	
A	556 SF
A/O	7 NET
OCC	79

Card reader access to be installed at new doors and vestibule entry

Remove and replace existing doors to match vestibule doors. Kawneer spec shown in exhibit B. All final dimensions to be verified/confirmed by contractor.

EXIT I.1 & I.2	
W	12'
W/O	0.20
CAP	720
ACT	41

EXISTING AREA OUTSIDE OF PROJECT SCOPE



EXIT I.3	
W	4'
W/O	0.30
CAP	160
ACT	41

MAX TRAVEL 77' TOTAL  
250' ALLOWABLE W/ SPRINKLER

EXIT I.1



ADA ACCESSIBLE

EXIT I.2

EXISTING N.N.W.

EXIT I.3

31'-5 1/4"

**TOTAL OCCUPANTS:**  
250 PEOPLE

Remove and replace glass system with metal doors. Scope of work to be defined on site and documentation to be finalized for bidding.